INFORMAL TENDER ADVERT

NELSON MANDELA BAY MUNICIPALITY
BUDGET AND TREASURY DIRECTORATE
PURCHASING AND STORES DIVISION

Tender Number: GQ11266574
Buyer: Dulwana, Miss Q [00065769]

Closing Date: 2026-11-23
Closing Time: 11:00 A.M

Telephone : 041 506 7630

REFER ALL ENQUIRIES TO THE BUYER

ITEM	QUANTITY	UNIT	KEY WORD	DESCRIPTION	REQUISITION
1	1.00	LOT	BUILDING MATERIAL	Supply and deliver building material as per specification and pricing schedule available at SCM in Harrower Road-Port Elizabeth. "Fully completed pricing schedule must be uploaded to the Informal Tender Portal by the stipulated closing date and time - failure to comply with this requirement will render the bid non-responsive and excluded fron further evaluation Samples and/or brochures may be requested from bidders after the tender closing date and time. Failure to provide the requested information within three (3) working days of the request, or within an alternative timeframe agreed to in writing with the relevant Project Manager, will render the bid non-responsive and excluded from further evaluation. "For more information on the above item please contact: Bomkazi Tshefu @ 061 537 9480.	AA84759

THE FOLLOWING CONDITIONS APPLY TO THIS INFORMAL TENDER

- BEFORE COMPLETING THIS FORM, SERVICE PROVIDERS MUST STUDY THE GENERAL CONDITIONS, DEFINITIONS AND DIRECTIVES APPLICABLE IN RESPECT OF SPECIFIC GOALS, AS PRESCRIBED IN THE PREFERENTIAL PROCUREMENT REGULATION OF 2022 THE 80/20 SYSTEM APPLIES TO THIS TENDER.
- Acceptance of this tender submission is subject to the General Conditions of Tender and Conditions of Purchase
- Acceptance of this tender is subject to successful registration on the Nelson Mandela Bay Supplier Database.
- For further information to register, please call Compliance Section @ 041 506 3274
- Failure to comply with these conditions may invalidate your tender submission.
- All tender prices should be valid for a minimum period of thirty (30) days from date of tender.
- ALL TENDER RESPONSES SHOULD BE COMPLETED ONLINE AND NO FAX SUBMISSION WILL BE ACCEPTED BY SUPPLY CHAIN UNIT.

Sports, Recreation, Arts & Culture

SUPPLY CHAIN MANAGEMENT

INFORMAL TENDER NO: GQ11266574

SPECIFICATION:

For the 100 m long × 0.8 m high sea wall, assuming 190 mm concrete blocks, plastered on both sides:

No.	Material	Quantity
1	190 mm concrete blocks	1,100 No.
2	Cement, 50 kg bags – blockwork	15 bags
3	Cement, 50 kg bags – plastering	22 bags
4	Total cement	40 bags *(rounded up)*
5	Building sand – blockwork mortar	2.0–2.2 m^3
6	Plaster sand	3.0–3.5 m^3
7	Galvanised brickforce	220 m
8	20 m brickforce rolls	11 rolls

Product specification:

- Cement: 50 kg bags, new and sealed, suitable for construction purposes and compliant with SANS 50197-1
- Bricks Compliant with SANS 1215.
- Brick force: Manufactured from hard-drawn steel wire, welded at intersections.
- Building sand: Clean, suitable for building and plastering, free from excessive clay, organic matter and other harmful substances.

Minimum requirements

- Product samples/ Brochure: The municipality reserves the right to request samples of quoted materials before award ~~or during the contract period.~~

General Notes:

1. Work to commence within (7) Seven working days after receiving order, failing which, the order will be cancelled, and a new order will be provided to the next highest point scoring service provider.

2. Service provider has 30 working days after receiving order to complete the work.

For further information, please contact:
Bomkazi Tshefu
Email: btshefu@mandelametro.gov.za
Cell: 061 537 9480

Public

nelson mandela bay MUNICIPALITY

Sports, Recreation, Arts & Culture

SUPPLY CHAIN MANAGEMENT

PRICING SCHEDULE NO: GQ11266574

"Fully completed pricing schedule to be uploaded on the Informal Tender Portal before the closing date and time of the advert- failure to do so may render you non responsive and be excluded from further evaluation

No.	Description	Unit	Qty	Price excl. vat	Rate (excl. vat)	Total incl. va
1	190mm Concrete blocks	No	1100		R	R
2	50kg cement bags	No	40		R	R
3	Building sand	m3	2.2		R	R
4	Plaster sand	m3	3.5		R	R
5	Brick force	Rolls	11		R	R
6	Delivery, off-loading and placement of materials at **Bluewater Bay Beach - Gqeberha**	Sum	1		R	R
					Total	**R**
					Add Vat 15%	**R**
					Total Amount	**R**

NAME OF THE SERVICE PROVIDER: .....

ADDRESS: .....

CONTACT DETAILS: .....

SIGNATURE: .....DATED: .....

Public